

Addendum No.3
for the
Northumberland County High/Middle School Sanitary
Treatment Modification Project

Prepared For
Northumberland County
72 Monument Place
Heathsville, VA 22473



Prepared by
C. Robert L. Mangrum, P.E., BCEE
Mangrum Consulting & Design
1500 Clayton Avenue
Lynchburg, VA 24503

Addendum Date: January 15, 2024

This Addendum No. 3, dated January 15, 2024 amends or supplements the Contract Documents titled Northumberland County High/Middle School Sanitary Treatment Modification Project Dated November 14, 2023 as indicated below:

Changes to Drawings:

Item 1: Sheet D-002, add the following:

“J. Forcemain Pressure Testing:

1. All pressure pipelines shall be thoroughly blown out under pressure and cleaned of foreign matter before testing. Care shall be taken to prevent objectionable matter from entering the piping systems.
2. All new force mains shall be pressure tested in accordance with ANSI/AWWA C600.
3. Force mains shall be filled with clean water and subjected to a hydrostatic pressure of 75 psi, measured at the highest point along the test section, for a period of 2 hours.
4. The test pressure shall not vary by more than +/- 5 psi for the duration of the test. The maximum allowable leakage in gallons shall be based on the AWWA C600-05 formula.
5. All temporary piping, test equipment, and blocking shall be provided by the Contractor.”

Changes to Project Manual:

None.

Questions & Responses:

None.

Attachments

None.

END OF ADDENDUM NO. 3